

# Homeland Hempcrete

Homeland Hempcrete provides cast-in-place hempcrete wall assemblies. The hemp insulation is cast in timber wood framing. This hempcrete is a mix of hemp hurd, water, lime, and pozzolan. Their pre-made, pre-cured high-quality hemp wall panels are perfect for custom designs. They focus on localized supply chains, servicing most of their own installations. You can also purchase prefabricated wall assembly kits of four 4x8ft panels, lead time is about 6-8 weeks.



CATEGORY	MANUFACTURER
Insulation / Fibrous, Cellulosic, Granular, Hemp	Homeland Hempcrete

**MATERIAL COMPOSITION\***  
SPF lumber, 41% Hemp Hurd, 45.5% High Calcium Hydrated Lime, 13.5% proprietary blend of natural pozzolans  
*\*as reported by the manufacturer*

- CERTIFICATIONS & DISCLOSURES**
- ☐ ~~Health Product Declaration (HPD)~~
  - ☐ ~~Declare Label~~
  - ☐ ~~Environmental Product Declaration (EPD)~~
  - ☐ ~~Safety Data Sheet (SDS)~~
  - ☐ ~~USDA Certified Biobased Product Label~~
  - ☐ ~~Other~~

**LAST UPDATED**  
June 20, 2023